

2024/2025

ENTERPRISE COMMERCE COMPANY NETWORK PROJECT

Made By:

Ahmed Salah Abduljalil AL-Qobati

Supervised By:

Dr. Nashwan Saeed

Case study:

A trading/Commerce floor Support center employs 600 staff. They have recently expanded and as a result, need to move to a new building. A building has been identified but has no network. This means that before they can make to move out, new network service needs to be designed and implemented in the new building. Existing Network comprises of the following elements: The new building is expected to have three floors with two departments in each for example;

1. **First floor-** (**Sales and Marketing Department**-120 users expected, **Human Resource and Logistics Department**-120 users expected).
2. **Second floor-** (**Finance and Accounts Department**-120 users expected, **Administrator and Public Relations Department**-120 users expected).
3. **Third floor-** (**ICT**-120 users expected, **Server Room**-12 devices expected).

Therefore, as a key member of the Networks Team, you have been tasked to design a network for the new building. At this stage, logical design is required, which shows the measures that you would put in place to ensure that the new network meets the current business need and is future-proofed

Network Requirements:

1. Use Cisco Packet Tracer to design and implement the network solution.
2. Use hierarchical model providing redundancy at every layer i.e. two routers and two multilayer switches are expected to be used to provide redundancy.

3. The network is also expected to connect to at least two ISPs to provide redundancy and each router to be connected to the two ISPs.
4. Each department is required to have a wireless network for the users.
5. Each department should be in a different VLAN and in different subnetwork.
6. Provided a base network of 172.16.1.0, carry out subnetting to allocate the correct number of IP addresses to each department.
7. The company network is connected to the static, public IP addresses (Internet Protocol) 195.136.17.0/30, 195.136.17.4/30, 195.136.17.8/30 and 195.136.17.12/30 connected to the two Internet providers.
8. Configure basic device settings such as hostnames, console password, enable password, banner messages, disable IP domain lookup.
9. Devices in all the departments are required to communicate with each other with the respective multilayer switch configured for inter-VLAN routing.
10. The Multilayer switches are expected to carry out both routing and switching functionalities thus will be assigned IP addresses.
11. All devices in the network are expected to obtain an IP address dynamically from the dedicated DHCP servers located at the server room.
12. Devices in the server room are to be allocated IP address statically.
13. Use OSPF as the routing protocol to advertise routes both on the routers and multilayer switches.

14. Configure SSH in all the routers and layer three switches for remote login.
15. Configure port-security for the Finance and Accounts department to allow only one device to connect to a switchport, use sticky method to obtain mac-address and violation mode shutdown.
16. Configure PAT to use the respective outbound router interface IPv4 address, implement the necessary ACL rule.
17. Test Communication, ensure everything configured is working as expected


Technologies Implemented:

1. Creating a network topology using Cisco Packet Tracer.
2. Hierarchical Network Design.
3. Connecting Networking devices with Correct cabling.
4. Configuring Basic device settings.
5. Creating VLANs and assigning ports VLAN numbers.
6. Subnetting and IP Addressing.
7. Configuring Inter-VLAN Routing on the Multilayer switches (Switch Virtual Interface).
8. Configuring Dedicated DHCP Server device to provide dynamic IP allocation.
9. Configuring SSH for secure Remote access.
10. Configuring OSPF as the routing protocol.
11. Configuring NAT Overload(Port Address Translation PAT).
12. Configuring standard and extended Access Control Lists ACL.
13. Configuring switchport security or Port-Security on the switches.

14. Configuring WLAN or wireless network (Cisco Access Point).
15. Host Device Configurations.
16. Configuring ISP routers.
17. Test and Verifying Network Communication.
18. Network Topology Created
19. The network topology below satisfy the user requirements above and everything is verified, tested and working fine

Network Topology:

The network topology below satisfy the user requirements above and everything is verified, tested and working fine.



Testing Connectivity:

The image displays a Cisco Packet Tracer network simulation. The network is divided into three main sections: FIRST-FLOOR, SECOND-FLOOR, and a central Core area. The FIRST-FLOOR section includes a Sales & Marketing VLAN 10 (NET: 172.16.1.0/25) with Sales-PC, Sales-Printer, Sales-AP, Sales-Laptop, and Sales-Tablet. The SECOND-FLOOR section includes an HR & Logistics VLAN 20 (NET: 172.16.1.128/25) with HR-PC, HR-Printer, HR-AP, HR-Laptop, and HR-Tablet. The Core area includes a Finance & Accounting VLAN 30 (NET: 172.16.2.0/25) with Finance-PC, Finance-Printer, Finance-AP, Finance-Laptop, and Finance-Tablet. A central Core-R1 router is connected to all three VLANs. A Command Prompt window is open, showing the following commands and output:

```
Cisco Packet Tracer PC Command Line 1.0
C:\>ssh -l admin 172.16.3.154
% Connection timed out; remote host not responding
C:\>ssh -l 172.16.3.154
Invalid Command.
C:\>ssh -l admin 172.16.3.154
% Connection timed out; remote host not responding
C:\>ssh -l admin 172.16.3.154
Password:
No Unauthorized Access!!!
CORE-R1>
CORE-R1>
CORE-R1>
```

The network diagram shows a central Core-R1 router connected to three VLANs. The FIRST-FLOOR section includes a Sales & Marketing VLAN 10 (NET: 172.16.1.0/25) with Sales-PC, Sales-Printer, Sales-AP, Sales-Laptop, and Sales-Tablet. The SECOND-FLOOR section includes an HR & Logistics VLAN 20 (NET: 172.16.1.128/25) with HR-PC, HR-Printer, HR-AP, HR-Laptop, and HR-Tablet. The Core area includes a Finance & Accounting VLAN 30 (NET: 172.16.2.0/25) with Finance-PC, Finance-Printer, Finance-AP, Finance-Laptop, and Finance-Tablet. A central Core-R1 router is connected to all three VLANs. A Command Prompt window is open, showing the following commands and output:

IP Addressing:

Base Network: 172.16.1.0

First Floor

Department	Network Address	Subnet Mask	Host Address Range	Broadcast Address
Sales & Marketing	172.16.1.0	255.255.255.128/25	172.16.1.1 to 172.16.1.126	172.16.1.127
HR & Logistics	172.16.1.128	255.255.255.128/25	172.16.1.129 to 172.16.1.254	172.16.1.255

Second Floor

Department	Network Address	Subnet Mask	Host Address Range	Broadcast Address
Finance & Accounting	172.16.2.0	255.255.255.128/25	172.16.2.1 to 172.16.2.126	172.16.2.127
Admin & Public Relations	172.16.2.128	255.255.255.128/25	172.16.2.129 to 172.16.2.254	172.16.2.255

Third Floor

Department	Network Address	Subnet Mask	Host Address Range	Broadcast Address
ICT	172.16.3.0	255.255.255.128/25	172.16.3.1 to 172.16.3.126	172.16.3.127
Server Room	172.16.3.128	255.255.255.240/28	172.16.3.129 to 172.16.3.142	172.16.3.143

Between The Routers and layer-3 Switches

No.	Network Address	Subnet Mask	Host Address Range	Broadcast Address
R1 – MLTSW1	172.16.3.144	255.255.255.252	172.16.3.145 to 172.16.3.146	172.16.3.147
R1 – MLTSW2	172.16.3.148	255.255.255.252	172.16.3.149 to 172.16.3.150	172.16.3.151
R2 – MLTSW1	172.16.3.152	255.255.255.252	172.16.3.153 to 172.16.3.154	172.16.3.155
R2 – MLTSW2	172.16.3.156	255.255.255.252	172.16.3.157 to 172.16.3.158	172.16.3.159

Between The Routers and ISPs

Public IP Addresses 195.136.17.0/30, 195.136.17.4/30, 195.136.17.8/30 and 195.136.17.12/30

Config Steps:

1. Basic settings to all devices + ssh on routers and layer - 3 switches.
2. VLANs assignment + all access and trunk ports on layer-2 and layer-3 switches.
3. Switchport security to finance department.
4. Subnetting and IP addressing.

5. OSPF on the routers and layer-3 switches.
6. Static IP address to Server Room devices.
7. DHCP server device configurations.
8. Inter-VLAN routing on the layer-3 switches + IP DHCP helper addresses.
9. Wireless Network Configuration.
10. PAT + ACL.
 - a. Default Static Route.
11. Verifying and testing the configurations.